# **Panasonic**

## REFERENCE SPECIFICATIONS

M/S

MODEL AC Servo Motor. MINAS A6 Series

MHMF (23bit Batteryless Absolute / 23bit Absolute)

Issued on Jun. 9. 2020

Changed on

Industrial Device Solution Business Unit, Industrial Device Business Division Industrial Solutions Company, Panasonic Corporation

7-1-1 Morofuku, Daito-City, Osaka 574-0044 Japan

If you have any questions, please contact the seller (Sales office or Distributor) of the product.

| Checked  | Checked   | Designed |
|----------|-----------|----------|
| L. Oggun | No Obranz | R. Yano  |



| 1 |  |
|---|--|
|   |  |

| Date     | Page | Sym.                                    | REVISION     | Signed |
|----------|------|---|--------------|--------|
| 2020.6.9 |      | *************************************** | NEWLY ISSUED | R.YANO |
|          |      |   |              |        |
|          |      |   |              |        |
|          |      |   |              |        |
|          |      |   |              |        |
|          |      |   |              | •      |
|          |      |   |              |        |
|          |      |   |              |        |
|          |      |   |              |        |
|          |      |   |              |        |
|          |      |   |              |        |
|          |      |   |              |        |
|          |      |   |              |        |
|          |      |   |              |        |
|          |      | *************************************** |              |        |
|          |      |   |              |        |
|          |      |   |              |        |
|          |      |   |              |        |
|          |      | ••••••                                  |              |        |
|          |      |   |              |        |
|          |      |   |              |        |
|          |      |   |              |        |
|          |      |   |              |        |
|          |      |   |              |        |
|          |      |   |              |        |
|          |      |   |              |        |
|          |      |   |              |        |
|          |      |   |              |        |
|          |      |   |              |        |
|          |      |   |              |        |
|          |      |   |              |        |
|          |      |   |              |        |
|          |      |   |              |        |
|          |      |   |              |        |
|          |      |   |              |        |
|          |      | L                                       | <u> </u>     |        |

#### 1. Scope

This specification relates to the servo motor of an AC servo system manufactured and delivered by Industrial Device Solution Business Unit, Industrial Device Business Division, Industrial Solutions Company, Panasonic Corporation.

This product is intended for industrial equipment. It cannot be used for any other Purposes (e.g. for household).

### 2. Applicable models, Specifications, Outline drawings.

| Applicable models | Specifications |     | Outline drawings |
|-------------------|----------------|-----|------------------|
| MHMF024□1△9M      | SX-DSV03571    | 5-1 | SX-DSV0357101    |
| MHMF044□1△9M      |                | 5-2 | 1                |
| MHMF084□1△9M      |                | 5-3 | SX-DSV0357102    |
| MHMF094□1△9M      |                | 5-4 | 1                |

#### ☐ shows rotary encoder specification

| Encoder Specification      | Symbol "□" |
|----------------------------|------------|
| 23bit Batteryless Absolute | A          |
| 23bit Absolute             | L          |

#### $\triangle$ shows motor structure

| Oil Seal | Motor Brake | Shaft         |                  |  |
|----------|-------------|---------------|------------------|--|
| On Sear  | Motor Brake | Straight type | With key and tap |  |
| Without  | Without     | A             | S                |  |
|          | With        | В             | Т                |  |
| With     | Without     | С             | U                |  |
|          | With        | D             | V                |  |

#### 3. Motor brake specification

|   |                                    | Applicable motors  |                    |  |
|---|------------------------------------|--------------------|--------------------|--|
| Items                                     | Units                              | MHMF024<br>MHMF044 | MHMF084<br>MHMF094 |  |
| Static friction torque *1                 | N∙m                                | 1.6 or more        | 3.8 or more        |  |
| Rotary part inertia *2                    | 10 <sup>-4</sup> kg·m <sup>2</sup> | 0.018              | 0.075              |  |
| Armature pull in time *2                  | ms                                 | 50 or less         | 70 or less         |  |
| Armature release time *2                  | ms                                 | 20 or less **3     | <b>←</b>           |  |
| Release voltage *1                        | DC,V                               | 1 or more          | <b>←</b>           |  |
| Suction voltage *1                        | DC,V                               | 24±2.4             | <b>←</b>           |  |
| Rated current (at DC24 V) *2              | DC,A                               | 0.36               | 0.42               |  |
| Allowable braking energy ; 1 time each *2 | J                                  | 105                | 185                |  |
| All allowable braking<br>Energy *2        | J                                  | 44.1×10³           | 80.0×10³           |  |
| Allowable angular acceleration *2         | rad/s²                             | 30000              | <b>←</b>           |  |


- \*1 Value of our delivery inspection.
- \*2 Representative value at 20 °C.
- \*3 By varistor (TND14V271K made by Nippon Chemi-con Corporation.)
- (1) This brake is non-excited operation type brake.
- (2) Armature pull in time and Armature release time are delay time of brake operation. Please confirm these by actual machine when motor is used.
- (3) When the motor was forwarded, the brake's backlash is 2 ° or less.
- (4) Power supply for motor brake must be prepared by user side. (Either way of connection for polarity would be acceptable)
- (5) The above-mentioned all allowable braking energy shall be braking energy complying with the brake specification (Braking energy capable of performing a suction motion in consideration of brake temperature increases).
- (6) The motor life with the repetitions of acceleration and deceleration at the above allowable angular acceleration: 10 million times.(The number of acceleration-deceleration cycles until brake's backlash changes rapidly)
- (7) The series connection of the protection parts such as fuses is recommended in the case of the use with varistor.


| Items                             | Units   | MHMF024□1△9M<br>(Without brake)     | MHMF024 $\square$ 1 $\triangle$ 9M MHMF024 $\square$ 1 $\triangle$ 9M (Without brake) (With brake) |                     |
|-----------------------------------|---|-------------------------------------|--|---------------------|
| Rated output                      | W   | 200                                 | <del></del>  |                     |
| Rating                            | %   | (*100)                              | <del></del>  | * refer to the      |
| Number of poles                   |   | 10                                  | <del></del>  | characteristic      |
| Rated speed                       | r/min   | 3000                                | <del></del>  | curve below         |
| Max. speed                        | r/min   | 6500                                | <del></del>  |                     |
| Rated torque                      | N∙m   | 0.64                                | <del></del>  |                     |
| Continuous stall torque           | N⋅m   | 0.76                                | <del></del>  |                     |
| Max. torque                       | N·m   | 2.23                                | <del></del>  |                     |
| Rated current                     | A(rms)  | (0.8)                               | <del></del>  |                     |
| Stall current                     | A(rms)  | (0.9)                               | <del></del>  |                     |
| Rotor inertia                     | $\times 10^{-4} \mathrm{kg} \cdot \mathrm{m}^2$ | 0.29                                | 0.31   |                     |
| Electrical time constant          | ms  | (2.0)                               | <del></del>  |                     |
| Mechanical time constant          | ms  | 1.92                                | 2.06   |                     |
| Power rate                        | kW/s  | 14.1                                | 13.2   |                     |
| Momentary max. current            | A(0-p)  | (3.8)                               | <del></del>  |                     |
| Demagnetization current           | A(0-p)  | 6.0                                 | <del></del>  |                     |
| Voltage constant per phase        | ×10 <sup>-3</sup> V(rms)/min <sup>-1</sup>      | 30.6±10 %                           | <del></del>  |                     |
| Excitation voltage constant       | ×10 <sup>-3</sup> V(0-p)/min <sup>-1</sup>      | 64.9±10 %                           | <b>———</b>   |                     |
| Torque constant                   | N·m/A(rms)                                      | 0.88±10 %                           | <b>———</b>   |                     |
|                                   | N·m/A(0-p)                                      | 0.62±10 %                           | <del></del>  |                     |
| Phase resistance                  | Ω   | 17.0±7 %                            | <del></del>  |                     |
| Phase inductance                  | mH  | (34.7)                              | <del></del>  | * Center Value      |
| Thermal class                     |   | 155(F)                              | <b>←</b>   |                     |
| Vibration class                   |   | V-15                                | <del></del>  |                     |
| Paint color                       |   | Partially Silver<br>Partially Black | <del></del>  | Plastic part :Black |
| Mass                              | kg  | 0.98                                | 1.4  |                     |
| Structure                         | _   | Totally-enclosed self-cooled type   | <del></del>  |                     |
| Servo driver power supply voltage | V AC  | 400                                 | <del></del>  |                     |

- This specification is guaranteed after combining and adjusting with the servo driver. (Representative value at 20 °C)
- · Rated torque is the result that have been considered dispersions of motor specification refer to Appendix 5-5.
- · Set the temperature of center of frame to 75 °C or less. (When ambient temperature is 40 °C)
- · Speed Torque characteristic (Representative value)

Servo driver power supply voltage: at AC 400 V

Dotted line indicates fall of servo driver power supply voltage by 10 %







| Items                             | Units   | MHMF044□1△9M<br>(Without brake)     | $\begin{array}{c cccc} MHMF044 \square 1 \triangle 9M & MHMF044 \square 1 \triangle 9M \\ (Without brake) & (With brake) \end{array}$ |                     |
|-----------------------------------|---|-------------------------------------|---|---------------------|
| Rated output                      | W   | 400                                 | <b>*************************************</b>  |                     |
| Rating                            | %   | (*100)                              | <del></del>   | * refer to the      |
| Number of poles                   |   | 10                                  | <del></del>   | characteristic      |
| Rated speed                       | r/min   | 3000                                | <del></del>   | curve below         |
| Max. speed                        | r/min   | 6500                                | <del></del>   |                     |
| Rated torque                      | N·m   | 1.27                                | <del></del>   |                     |
| Continuous stall torque           | N·m   | 1.40                                | <del></del>   |                     |
| Max. torque                       | N·m   | 4.46                                | <del></del>   |                     |
| Rated current                     | A(rms)  | (1.2)                               | <del></del>   |                     |
| Stall current                     | A(rms)  | (1.3)                               | <del></del>   |                     |
| Rotor inertia                     | $\times 10^{-4} \mathrm{kg} \cdot \mathrm{m}^2$ | 0.56                                | 0.58  |                     |
| Electrical time constant          | ms  | (2.4)                               | <del></del>   |                     |
| Mechanical time constant          | ms  | 1.46                                | 1.51  |                     |
| Power rate                        | kW/s  | 28.8                                | 27.8  |                     |
| Momentary max. current            | A(0-p)  | (5.7)                               | <del></del>   |                     |
| Demagnetization current           | A(0-p)  | 9.0                                 | <del></del>   |                     |
| Voltage constant per phase        | ×10 <sup>-3</sup> V(rms)/min <sup>-1</sup>      | 43.3±10 %                           | <del></del>   |                     |
| Excitation voltage constant       | ×10 <sup>-3</sup> V(0-p)/min <sup>-1</sup>      | 91.9±10 %                           | <del></del>   |                     |
| Torque constant                   | N⋅m/A(rms)                                      | 1.24±10 %                           | <del></del>   |                     |
|                                   | N·m/A(0-p)                                      | 0.88±10 %                           | <del></del>   |                     |
| Phase resistance                  | Ω   | 13.4±7 %                            | <del></del>   |                     |
| Phase inductance                  | mH  | (31.9)                              | <del></del>   | * Center Value      |
| Thermal class                     |   | 155(F)                              | <del></del>   |                     |
| Vibration class                   | _   | V-15                                | <del></del>   |                     |
| Paint color                       | _   | Partially Silver<br>Partially Black | <b>←</b>  | Plastic part :Black |
| Mass                              | kg  | 1.4                                 | 1.8   |                     |
| Structure                         | _   | Totally-enclosed self-cooled type   | <b>———</b>  |                     |
| Servo driver power supply voltage | V AC  | 400                                 | <del></del>   |                     |

- This specification is guaranteed after combining and adjusting with the servo driver. (Representative value at 20 °C)
- · Rated torque is the result that have been considered dispersions of motor specification refer to Appendix 5-5.
- · Set the temperature of center of frame to 85 °C or less. (When ambient temperature is 40 °C)
- · Speed Torque characteristic (Representative value)

Servo driver power supply voltage: at AC 400 V

Dotted line indicates fall of servo driver power supply voltage by 10 %







| Items                             | Units                                      | MHMF084□1△9M<br>(Without brake)     | MHMF084□1△9M<br>(With brake) | Remarks             |
|-----------------------------------|--|-------------------------------------|------------------------------|---------------------|
| Rated output                      | W  | 750                                 | <del></del>                  |                     |
| Rating                            | %  | (*100)                              |                              | * refer to the      |
| Number of poles                   | _  | 10                                  | <del></del>                  | characteristic      |
| Rated speed                       | r/min                                      | 3000                                | <del></del>                  | curve below         |
| Max. speed                        | r/min                                      | 6000                                | <del></del>                  |                     |
| Rated torque                      | N∙m  | 2.39                                | <del></del>                  |                     |
| Continuous stall torque           | N⋅m  | 2.86                                | <del></del>                  |                     |
| Max. torque                       | N⋅m  | 8.36                                | <del></del>                  |                     |
| Rated current                     | A(rms)                                     | (2.1)                               | <del></del>                  |                     |
| Stall current                     | A(rms)                                     | (2.5)                               | <del></del>                  |                     |
| Rotor inertia                     | ×10 <sup>-4</sup> kg·m <sup>2</sup>        | 1.56                                | 1.66                         |                     |
| Electrical time constant          | ms   | (5.7)                               | <del></del>                  |                     |
| Mechanical time constant          | ms   | 0.92                                | 0.98                         |                     |
| Power rate                        | kW/s                                       | 36.6                                | 34.4                         |                     |
| Momentary max. current            | A(0-p)                                     | (10.3)                              | <del></del>                  |                     |
| Demagnetization current           | A(0-p)                                     | 15                                  | <del></del>                  |                     |
| Voltage constant per phase        | ×10 <sup>-3</sup> V(rms)/min <sup>-1</sup> | 44.1±10 %                           | <del></del>                  |                     |
| Excitation voltage constant       | ×10 <sup>-3</sup> V(0-p)/min <sup>-1</sup> | 93.6±10 %                           | <del></del>                  |                     |
| Torque constant                   | N⋅m/A(rms)                                 | 1.26±10 %                           | <del></del>                  |                     |
|                                   | N·m/A(0-p)                                 | 0.89±10 %                           | <del></del>                  |                     |
| Phase resistance                  | Ω  | 3.12±7 %                            | <del></del>                  |                     |
| Phase inductance                  | mH   | (17.9)                              | <del></del>                  | * Center Value      |
| Thermal class                     |  | 155(F)                              | <del></del>                  |                     |
| Vibration class                   |  | V-15                                | <del></del>                  |                     |
| Paint color                       | _  | Partially Silver<br>Partially Black | <b>←</b>                     | Plastic part :Black |
| Mass                              | Kg   | 2.4                                 | 3.2                          |                     |
| Structure                         | _  | Totally-enclosed self-cooled type   | <del></del>                  |                     |
| Servo driver power supply voltage | V AC                                       | 400                                 | <del></del>                  |                     |

- This specification is guaranteed after combining and adjusting with the servo driver. (Representative value at 20 °C)
- · Rated torque is the result that have been considered dispersions of motor specification refer to Appendix 5-5.
- Set the temperature of center of frame to 75 °C or less. (When ambient temperature is 40 °C)
- · Speed Torque characteristic (Representative value)

Servo driver power supply voltage: at AC 400 V

Dotted line indicates fall of servo driver power supply voltage by 10 %







| Items                             | Units   | MHMF094□1△9M<br>(Without brake)     | MHMF094□1△9M<br>(With brake) | Remarks             |
|-----------------------------------|---|-------------------------------------|------------------------------|---------------------|
| Rated output                      | W   | 1000                                | <del></del>                  |                     |
| Rating                            | %   | (*100)                              | <del></del>                  | * refer to the      |
| Number of poles                   |   | 10                                  | <del></del>                  | characteristic      |
| Rated speed                       | r/min   | 3000                                | <del></del>                  | curve below         |
| Max. speed                        | r/min   | 6000                                | <del>(</del>                 |                     |
| Rated torque                      | N⋅m   | 3.18                                | <del></del>                  |                     |
| Continuous stall torque           | N·m   | 3.34                                | <del></del>                  |                     |
| Max. torque                       | N·m   | 11.1                                | <del></del>                  |                     |
| Rated current                     | A(rms)  | (3.1)                               | <del></del>                  |                     |
| Stall current                     | A(rms)  | (3.3)                               | <del></del>                  |                     |
| Rotor inertia                     | $\times 10^{-4} \mathrm{kg} \cdot \mathrm{m}^2$ | 2.03                                | 2.13                         |                     |
| Electrical time constant          | ms  | (5.9)                               | <del></del>                  |                     |
| Mechanical time constant          | ms  | 0.84                                | 0.89                         |                     |
| Power rate                        | kW/s  | 49.8                                | 47.5                         |                     |
| Momentary max. current            | A(0-p)  | (15.5)                              | <del></del>                  |                     |
| Demagnetization current           | A(0-p)  | 23                                  | <del></del>                  |                     |
| Voltage constant per phase        | ×10 <sup>-3</sup> V(rms)/min <sup>-1</sup>      | 40.4±10 %                           | <del></del>                  |                     |
| Excitation voltage constant       | ×10 <sup>-3</sup> V(0-p)/min <sup>-1</sup>      | 85.7±10 %                           | •                            |                     |
| Torque constant                   | N⋅m/A(rms)                                      | 1.16±10 %                           | <b>←</b>                     |                     |
|                                   | N·m/A(0-p)                                      | 0.82±10 %                           | <del></del>                  |                     |
| Phase resistance                  | Ω   | 1.86±7 %                            | <del></del>                  |                     |
| Phase inductance                  | mH  | (11.0)                              | <del></del>                  | * Center Value      |
| Thermal class                     |   | 155(F)                              | <b>←</b>                     |                     |
| Vibration class                   |   | V-15                                | <b>←</b>                     |                     |
| Paint color                       | _   | Partially Silver<br>Partially Black | <b>←</b>                     | Plastic part :Black |
| Mass                              | kg  | 2.8                                 | 3.6                          |                     |
| Structure                         | _   | Totally-enclosed self-cooled type   | <del></del>                  |                     |
| Servo driver power supply voltage | V AC  | 400                                 | <del></del>                  |                     |

- This specification is guaranteed after combining and adjusting with the servo driver. (Representative value at 20 °C)
- · Rated torque is the result that have been considered dispersions of motor specification refer to Appendix 5-5.
- · Set the temperature of center of frame to 75 °C or less. (When ambient temperature is 40 °C)
- · Speed Torque characteristic (Representative value)

Servo driver power supply voltage: at AC 400~V


Dotted line indicates fall of servo driver power supply voltage by 10 %





#### • Test method

| Applicable models | Reference | Flange size | Flange material |
|-------------------|-----------|-------------|-----------------|
| MHMF024□1△9M      | Fig. 1    | 130×120×t12 | Aluminum        |
| MHMF044□1△9M      | 1         | 1           | 1               |
| MHMF084□1△9M      | <b>↑</b>  | 170×160×t12 | 1               |
| MHMF094□1△9M      | 1         | 1           | 1               |



#### Encoder: AGC047N0000050A000


|         | Sig                     | nal      |  |
|---------|-------------------------|----------|--|
| Pin No. | Batteryless<br>Absolute | Absolute |  |
| 1       | E0 V                    | E0 V     |  |
| 2       | E5 V                    | E5 V     |  |
| 3       | PS(SD)                  | PS(SD)   |  |
| 4       | PS(SD)                  | PS(SD)   |  |
| 5       | NC                      | NC       |  |
| 6       | NC                      | NC       |  |
| 7       | NC                      | BAT-     |  |
| 8       | NC                      | BAT+     |  |
| 9       | FG                      | FG       |  |
| 10      | NC                      | NC       |  |
| 11      | NC                      | NC       |  |
| 12      | NC                      | NC       |  |
|         |                         |          |  |




### Motor:

| 36C863N0000051A000 |               |            |  |  |  |  |
|--------------------|---------------|------------|--|--|--|--|
| Pin No.            | Sig           | nal        |  |  |  |  |
| PIN NU.            | Without Brake | With Brake |  |  |  |  |
| 1                  | NC            | Brake      |  |  |  |  |
| 2                  | υ             | U          |  |  |  |  |
| 3                  | V             | ٧          |  |  |  |  |
| 4                  | W             | W          |  |  |  |  |
| 5                  | NC NC         | Brake      |  |  |  |  |
| 6                  | NC            | NC         |  |  |  |  |
| Е                  | GND           | GND        |  |  |  |  |
|                    |               |            |  |  |  |  |


Connector specification





163° ±3°




163° ±3°











| Mode l       | Motor brake | Output<br>(W) | LL    | LR | LM   | S  | KB1  | KB2  |
|--------------|-------------|---------------|-------|----|------|----|------|------|
| MHMF02401Δ9M | Without     | 200           | 85.8  | 30 | 59.5 | 11 | 42.7 | 71.5 |
| MHMF04401Δ9M | 1           | 400           | 102.8 | 1  | 76.5 | 14 | 59.7 | 88.5 |
| MHMF02401Δ9M | With        | 200           | 115.3 | 1  | 89   | 11 | 42.7 | 101  |
| MHMF04401Δ9M | İ           | 400           | 132.3 | 1  | 105  | 14 | 59.7 | 118  |
|              |             |               |       |    |      |    |      |      |

- 1. The assembling precision conforms to the Japan Machine Tool Association Standard (MAS402-1981). (TIR value)
  - ·Shaft end runout: 0.015 (shaft exit middle)
- Squareness of flange face to shaft: 0.04 (070)
  Eccentricity of flange fitting outside diameter to shaft: 0.03 (middle of spigot)

  For flange mounting bolts, use hexagonal socket
- head bolts.





Detail of shaft step part (S=Free) (200 W only)

| 1 | Scale        | Panasonic Corporation    |         |         | Agreement |          | MHMF0◊4□1Δ9M □60 |  |  |
|---|--------------|--------------------------|---------|---------|-----------|----------|------------------|--|--|
| I |              | 3rd Angle System Unit:mm |         |         |           | Model    | MUMUATTARM ODA   |  |  |
|   | 1 ' 1        |                          |         |         |           |          | OUTLINE DRAWING  |  |  |
|   | Designed     | Drawn                    | Checked | Checked | Checked   | Name     | OUTLINE DRAWING  |  |  |
|   | YANO         | YANO                     | TAMURA  | OKUNO   | DGAWA     | No.      | SX-DSV0357101    |  |  |
| 1 | 2222 /22 /22 |                          | / /     | ( (     | ( (       | 1 1 10 - | 1 3/ 03/033/101  |  |  |

## Encoder: AGC047N0000050A000


|        | Sig                     | nal      |  |  |
|--------|-------------------------|----------|--|--|
| in No. | Batteryless<br>Absolute | Absolute |  |  |
| 1      | E0 V                    | E0 V     |  |  |
| 2      | E5 V                    | E5 V     |  |  |
| 3      | PS(SD)                  | PS(SD)   |  |  |
| 4      | PS(SD)                  | PS(SD)   |  |  |
| 5      | NC                      | NC       |  |  |
| 6      | NC                      | NC       |  |  |
| 7      | NC                      | BAT~     |  |  |
| 8      | NC                      | BAT+     |  |  |
| 9      | FG                      | FG       |  |  |
| 10     | NC                      | NC       |  |  |
| 11     | NC                      | NC       |  |  |
| 12     | NC                      | NC       |  |  |
|        |                         |          |  |  |





Motor: BGC863N0000051A000


| Pin No. | Signal        |            |  |  |  |
|---------|---------------|------------|--|--|--|
|         | Without Brake | With Brake |  |  |  |
| 1       | NC            | Brake      |  |  |  |
| 2       | U             | U          |  |  |  |
| 3       | V             | ٧          |  |  |  |
| 4       | W             | W          |  |  |  |
| 5       | NC            | NC Brake   |  |  |  |
| 6       | 5 NC NC       |            |  |  |  |
| E       | GND           | GND        |  |  |  |


Connector specification












| Mode l       | Motor brake | Output<br>(W) | LL    | LR | LM    | S  | KB1  | кв2   |
|--------------|-------------|---------------|-------|----|-------|----|------|-------|
| MHMF084□1Δ9M | Without     | 750           | 109.9 | 35 | 83.6  | 19 | 65.7 | 95.6  |
| MHMF09401Δ9M | 1           | 1000          | 122.7 | 1  | 96.4  | 1  | 78.5 | 108.4 |
| MHMF08401Δ9M | With        | 750           | 143.5 | 1  | 117.2 | 1  | 65.7 | 129.2 |
| MHMF09401Δ9M | 1           | 1000          | 156.3 | 1  | 130   | 1  | 78.5 | 142   |
|              |             |               |       |    |       |    |      |       |

- The assembling precision conforms to the Japan Machine Tool Association Standard (MAS402-1981). (TIR value)

  - Shaft end runout: 0.015 (shaft exit middle)
    Squareness of flange face to shaft: 0.04 (090)
    Eccentricity of flange fitting outside diameter
    to shaft: 0.03 (middle of spigot)
- 2. For flange mounting bolts, use hexagonal socket



| Scale      | Panaso                   | nic Corpo  | ration     | Agreement  |                 | MHMF0♦4□1Δ9M □80           |  |
|------------|--------------------------|------------|------------|------------|-----------------|----------------------------|--|
|            | 3rd Angle System Unit:mm |            |            |            | Model           | MUML 0 4 4 1 7 3 M 1 1 0 0 |  |
| 1 1 1      |                          |            |            |            |                 |                            |  |
|            |                          |            | L          | Name       | OUTLINE DRAWING |                            |  |
| Designed   | Drawn                    | Checked    | Checked    | Checked    | 1 401110        |                            |  |
| YAND       | YANO                     | TAMURA     | OKUNO      | DGAWA      |                 | DV D0V00E7400              |  |
| 2020/06/09 | 2020/06/09               | 2020/06/09 | 2020/06/09 | 2020/06/09 | No.             | SX-DSV0357102              |  |